




FIRST-IN STATION ALERTING LEGEND			
MCU	Master Control Unit	FSSL	Strobe Light
TIM	Telephone Interface Module	ASLA	Alerting Strobe Light Adapter
CR	Control Remote	KL	Knight Light Strip
RIU	Radio Isolation Unit	DKL	Dual Knight Light Strip
DLSP	Data Line Surge Protector	KD	KL Dimmer Switch
PHS	Power Hub-Spoke & UPS - REQUIRES 110V. POWER	HPA	HPA Amplifier
PLC	Power Light Controller & UPS -REQUIRES 110V. POWER	HPA	HPA Speaker
SC	Satellite Controller	TT	Turnout Timer
S	Satellite	DB	Doorbell
DR	Dorm Remote	ES	Emergency Switch
DL	Dorm Light	SW	Speaker Switch
AED	Alerting Endpoint Display REQUIRES 110V. POWER	4SQ	4 Square Junction Box

KEYED NOTES	
ALL CONDUIT 1/2" UNLESS OTHERWISE SPECIFIED	
11	BUTTON OR SWITCH ASSEMBLY. 4 SQUARE W/ SINGLE RING. BOX MOUNTED AT +48" AFF. CONDUIT TO ACCESSIBLE SPACE.
12	ALERTING ENDPOINT(AED) AND TURNOUT TIMER(TT). SINGLE 4 SQUARE J-BOX W/ 1-GANG RING MOUNTED AT +8'-0" AFF. CONDUIT TO ACCESSIBLE SPACE. NETWORK DROP IN SAME BOX. KEEP CLEAR OF OBSTRUCTIONS. 120VAC FOR TV AT SAME HEIGHT.
13	HPA SPEAKERS. SINGLE 4 SQUARE J-BOX MOUNTED AT +10'-12" AFF CONDUIT TO ADJACENT HPA AMPLIFIER AS SHOWN. KEEP CLEAR OF OBSTRUCTIONS.
14	HPA AMPLIFIER. 10X8X4 HOFFMAN FLUSH WITH MASONRY. HEIGHT IS FLEXIBLE. KEEP CLEAR OF OBSTRUCTIONS. CONDUIT TO ADJACENT SPEAKERS AS SHOWN AND TO ACCESSIBLE CEILING SPACE.
15	SC AND S. 10X8X4 HOFFMAN AT 12' AFF MAX. CONDUIT TO ACCESSIBLE SPACE. CAN LINK WITH OTHER ALERTING DEVICES AS SHOWN.
16	4 SQUARE BOX AT CEILING. LIGHTS HANG ON CABLES. CONDUIT TO ACCESSIBLE SPACE. KEEP CLEAR OF OBSTRUCTIONS.
17	ALERTING ENDPOINT(AED). SINGLE 4 SQUARE J-BOX W/ 1-GANG RING. HEIGHT TO BE COORDINATED WITH OWNER. CONDUIT TO ACCESSIBLE SPACE. NETWORK DROP IN SAME BOX. KEEP CLEAR OF OBSTRUCTIONS. 110VAC FOR TV AT SAME HEIGHT.
18	STROBE LIGHT(FSSL). LVI PROVIDED CUSTOM BACK BOX, 9" L x 3" W. MOUNTED WITH LONG SIDE VERTICAL AT 72" AFF. CONDUIT TO ACCESSIBLE SPACE. CAN BE LINKED WITH OTHER ALERTING DEVICES AS SHOWN.



CITY OF THORNTON
FIRE STATION #8
15343 MONACO STREET
THORNTON, COLORADO 80602

ALLRED & ASSOCIATES
ARCHITECTURE | PLANNING | INTERIOR DESIGN
580 BUREAU STREET, SUITE 125, BROOMFIELD, COLORADO 80020
PHONE: 303.465.4306
www.allredarch.com

PRE-FINAL (PERMIT SET) • JOB NO. 2309

REVISION NAME		DATE

ISSUE DATE: 2024 0621

ALERTING PLAN

FSA.01

1 MAIN LEVEL ALERTING PLAN
N.T.S.

2 MEZZANINE ALERTING PLAN
N.T.S.

01 ALERT SYSTEM DEVICE SCHEDULE
SCALE : N.T.S.




ALLRED & ASSOCIATES

- JOB NO. 2309



PRE-FINAL (PERMIT SET)

THORNTON, COLORADO 80602


FSA.02



01 MASTER CONTROL UNIT – MCU
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.



02 CONTROL REMOTE – CR
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.



03 TELEPHONE INTERFACE MODULE – TIM
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

MCU MASTER CONTROL UNIT



- THE MASTER CONTROL UNIT IS THE COMMAND CENTER OF THE SMART STATION NETWORK.
- THE MASTER CONTROL UNIT SHALL ACCEPT ALARM INPUTS FROM UP TO (4) RADIOS, DEDICATED PHONE LINES, POTS TELEPHONE LINES, SERIAL DATA LINES, AS WELL AS TCP/IP ETHERNET NETWORKS.
- THE MASTER CONTROL UNIT SUPPORTS THE FULL ZIR COMMAND SET.
- THE MASTER CONTROL UNIT SHALL MEET THE NFPA REQUIREMENT 1221 FOR SUPERVISED COMMUNICATIONS FOR ALERTING WITH THE DISPATCH CENTER.
- ALARM AUDIO LEVELS SHALL BE CONTROLLABLE OVER A (30) DECIBAL RANGE IN (1) DECIBAL INCREMENTS.
- RADIO AUDIO LEVELS SHALL BE CONTROLLABLE OVER A (30) DECIBAL RANGE IN (1) DECIBAL INCREMENTS.
- THE ENTIRE FIRE STATION ALERTING LEVEL SHALL BE AUTOMATICALLY REDUCED AT NIGHT AND RETURNED TO NORMAL LEVELS IN THE MORNING AUTOMATICALLY.
- OUTSIDE SPEAKERS SHALL BE AUTOMATICALLY TURNED OFF AT NIGHT AND TURNED BACK ON IN THE MORNING AUTOMATICALLY.
- PRIMARY PROGRAMMING SHALL BE ACCOMPLISHED FROM THE FRONT PANEL, WHILE SECONDARY PROGRAMMING IS ACCOMPLISHED WITH THE SMART STATION SERVICE VIA COMPUTER.
- FRONT PANEL PROGRAMMING SHALL BE LIMITED TO PLACING THE STATION ON RADIO WATCH OR REMOVING THE STATION FROM RADIO WATCH.
- THE MASTER CONTROL UNIT SHALL BE POWERED FROM AN "ON-LINE" UPS FOR UNINTERRUPTIBLE ALERTING SERVICE.

CR CONTROL REMOTE

- WHEN THE ALARM SYSTEM TRIGGERS, THE CONTROL REMOTE CAN SHUT OFF GAS APPLIANCES, OPEN BAY DOORS, TURN ON BAY LIGHTS, OPEN GATES, SENSE DOOR TROUBLE, AND/OR SENSE INPUTS FROM CO2 DETECTORS IN APPARATUS BAYS.
- PROVIDES (8), DOUBLE POLE, DOUBLE THROW (DPDT) RELAYS UNDER SOFTWARE CONTROL FROM THE MASTER CONTROL UNIT.
- PROVIDE (4) REMOTE SENSING INPUTS TO COLLECT DATA RELEVANT TO THE CONTROL FUNCTIONS.
- ENABLES THE MASTER CONTROL UNIT TO OPERATE FIRE STATION ALERTING EQUIPMENT THAT IS NOT SMART STATION COMPATIBLE.
- ALL RELAYS SHALL BE ZONE, TIME DELAY AND TIME OF DAY CONTROLLABLE IN ANY COMBINATION NECESSARY.
- SHALL PROVIDE CONTROL AND SENSE CAPABILITY THROUGHOUT THE NETWORK AT ANY LOCATION.
- RELAYS SHALL BE RATED AT (5) AMPS AT (24) VOLTS DC OR AC.
- MECHANICAL LIFE OF THE RELAY CONTACTS SHALL BE A MINIMUM OF (5) MILLION OPERATIONS.
- RELAYS SHALL BE USED TO CONTROL THE OVEN/RANGES IN THE KITCHEN, OPERATION OF EACH APPARATUS BAY DOOR INDEPENDANTLY, AND CONNECTION OF CARBON MONOXIDE SENSORS TO THE SYSTEM. COORDINATE ALL ELECTRICAL CONTACTS AND RELAYS REQUIRED FOR LINE VOLTAGE CIRCUITS TO INTERFACE WITH CONTROL REMOTE DEVICES.
- WESTNET ALERT SYSTEM PROVIDES ONLY DRY CONTACTS RATED AT 24 VOLTS MAX, NO VOLTAGE IS SUPPLIED

TIM TELEPHONE INTERFACE MODULE

- SHALL BE UTILIZED FOR PAGING PERSONNEL WITHIN THE FIRE STATION.
- SHALL INTEGRATE THE FIRE STATION TELEPHONE SYSTEM INTO ALL AUDIO UNITS, SUCH AS COMBINATION SPEAKER/LED LIGHT DEVICES. PROGRAMMABLE SPEAKER/RED GLOW LIGHT DEVICES AND HIGH POWER AMPLIFIERS.
- REQUIRES CONDUIT SLEEVE TO STATION TELE/COMM ROOM



04 RADIO ISOLATION UNIT – RIU
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

RIU

RADIO ISOLATION UNIT

- SURGE PROTECTION DEVICE CONNECTED TO RADIO ANTENNAS EXTEND GROUND WIRE FROM UNIT TO LIGHTING PROTECTION SYSTEM.

ALERTING SYSTEM OVERVIEW PLEASE READ

Most contractors are unfamiliar with what the Alerting System is and the capabilities of the system. The overall function of the alerting system is to increase the response time of the received calls from 15 to 45 seconds using visual and audio alerts for dispatched units. This system is installed as a large communication loop utilizing CAT 5 cabling with very limited connections to the existing building.

There are several common questions that are generally asked during the rough in stages for our system:

Does the back box specified need to be a Hoffman Brand – Part #43050 – Cat #A–SE10x8x4 for Dorm Remotes (DR) and Satellite Controllers (SC)? YES, the mounting flanges for these devices specifically made for this type of box. This eliminates re–tapping of the box and quicker installation time.

Can power receptacles be relocated? YES, at a maximum of six (6) feet from plan indication.

Can conduit differ from plans? MAYBE, the routing of the conduit is very specific and is the link from device to device creating the overall communication loop, verify changes with LVI.

There is a spacing conflict with the Dorm Remote (DR), Thermostat, Light Switch, and Telephone location next to the door jamb. Can this be relocated? YES, this can be moved away from the door jamb, generally between the light switch and thermostat is most common, for the occupants to monitor their dispatched calls. Refer to notes on AS.01. The mounting flange will require 18" space between light switch and next device for the horizontally mounted Hoffman back box.

Can devices be relocated? YES, but at a maximum of six (6) feet. Please keep in mind of equal spacing of devices for an even audio and visual coverage; this is important when announcing dispatched calls. Also, the cabling is pre–manufactured and is designated for that device. Relocation of devices at more than six (6) feet from indicated location will need approval BY LVI.

How is the Hoffman Brand – Part #43050 – Cat #A–SE10x8x4 boxes to be mounted? For Dorm Remotes (DR), the back box is to mount horizontally, 10" wide and 8" tall, recessed 1/8" into the sheetrock wall, at 48" to centerline, above finished floor. The mounting flange covers the back box opening and pulls flush against the sheetrock.

For Satellite Controllers (SC), that is to be mounted into sheetrock ceilings, the back box will run, the 10" side, with the length of the room, in the center, free from obstructions, avoiding other trades, recessed 1/8" into sheetrock, and mounted at a maximum of 15' above finished floor. Back boxes installed in open areas will be mounted at a maximum of 15' above finished surface, free from obstructions, avoiding other trades, recessed 1/8" into sheetrock, and mounted at a maximum of 15' above finished floor. Back boxes installed in open areas will be mounted at a maximum of 15' above finished surface, free from obstructions, with length of room, and visible from all points in the rooms. Westnet does not assume the responsibility for poor installation of back boxes.

What is the function of the Control Remote (CR)? This device can perform multiple functions, opening apparatus bay doors, gates, shutting off equipment, kitchen stoves, appliances, corridor lighting, etc.

Any equipment that shows to be connected that are to be controlled by the CR will need a control voltage of 24 Volts that is NOT supplied BY LVI. The terminal rating is a maximum of 24V on the CR.

What is the MCU? This is the brains of the system. Received calls go thru this device and are announced throughout the system. This is most commonly the only connection that is made to the existing communications. This is to be located within six (6) feet of the dispatch radio in watch room or communication center of station.

These are just a few of the issues that you may have questions about. There is to be no alteration of the system without the approval of Westnet.

All installation of devices and cabling are done BY LVI. If there are more questions or concerns about the rough in for installation, please call:

LOW VOLTAGE INSTALLATIONS at (303)–250–6870



ALLRED&ASSOCIATES

ARCHITECTURE | PLANNING | INTERIOR DESIGN

500 BURLING STREET, SUITE 125, BROOMFIELD, COLORADO 80020 PHONE 303.465.4306 www.allredarch.com


PRE-FINAL (PERMIT SET) • JOB NO. 2309

CITY OF THORNTON
FIRE STATION #8
15343 MONACO STREET
THORNTON, COLORADO 80602


REVISION NAME DATE

ISSUE DATE: 2024 0621


FSA.03



01 DORM REMOTE – DR
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.




DORM REMOTE WITH ATTACHED FACEPLATE
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.




02 DORM LIGHT – DL
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

DR DORM REMOTE WITH LIGHT


- SPEAKER/LIGHT DEVICES SHALL BE FIREFIGHTER PROGRAMMED TO ACTIVATE ON ALL ALARMS STARTING AT SHIFT CHANGE.
- THE DEVICE AUDIO SHALL BE ADJUSTED OVER A (60) DECIBLE RANGE IN (1) DECIBLE INCREMENTS TO AID IN THE REDUCTION OF AUDIBLE SHOCK THAT OCCURS WHEN THE FIREFIGHTER AWAKENS TO AN ALARM.
- THE LIGHTING SHALL INCREASE DURING THE FIRST FEW SECONDS OF THE ALARM SEQUENCE TO REDUCE OPTICAL SHOCK UPON AWAKENING.
- THE LIGHT OUTPUT SHALL BE ADJUSTABLE BY EACH FIREFIGHTER.
- THE TWO-LINE DISPLAY SHALL BE USED FOR DISPLAYING TEXT MESSAGING.
- THE DEVICE SHALL OPERATE UP TO (4) COMBINATION SPEAKER/LED LIGHT DEVICES FOR ZONE CONTROLLED SLEEP AREAS.
- THE DEVICE SHALL BE DESIGNED TO BE WALL OR ROOM DIVIDER MOUNTED AT (2) FEET ABOVE THE HEIGHT OF THE BED TO PROVIDE ILLUMINATION FOR THE BED AND THE FLOOR.
- THE DEVICE CAN BE SURFACE MOUNTED.
- ALL CONNECTIONS SHALL BE MODULAR PLUGS ENABLING RELOCATION OF DORM REMOTE WITH MINIMUM EFFORT.



DORM REMOTE / DORM LIGHT MOUNTING DETAIL



SATELLIGHT CONTROLLER MOUNTING DETAIL



03 SATELLIGHT CONTROLLER – SC
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

SATELLIGHT SPEAKER – S
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

FIRE STATION ALERT STROBE CONTROLLER
N.T.S.
RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.

SC SATELLIGHT CONTROLLER

- SHALL OPERATE ON A CAT 5e SMART STATION PRIMARY ALARM NETWORK, WHICH IS DRIVEN FROM THE MCU.
- OPERATE INDEPENDANTLY OR DRIVE UP TO 4 DEVICES DEPENDING UPON THE LOCATION IN THE FIRE STATION
- AUDIO OUTPUT SHALL BE CONTROLLED BY SOFTWARE FROM THE MASTER CONTROL UNIT.
- AUDIO OUTPUT SHALL BE ADJUSTABLE ACROSS A 90 DECIBAL RANGE.
- SHALL BE CAPABLE OF INTELEGENT SENSING AND CONTROL OF FIRE STATION SYSTEMS AND EQUIPMENT. CONTROLLER SHALL UTILIZE BI-DIRECTIONAL DATA THROUGHOUT THE SMART STATION NETWORK AND EXTEND CAPABILITY TO THE FIRE DEPARTMENT DIPATCH CENTER.
- SHALL BE MOUNTED IN THE CEILING TO PROVIDE ALARM COVERAGE THROUGHOUT THE STATION.
- ACOUSTICAL CEILING MOUNTING SECURES THE DEVICE TO THE T-BAR RAILS AND THE SUPERSTRUCTURE OF THE BUILDING.
- DRYWALL AND PLASTER CEILING MOUNTING HARDWARE SHALL UTILIZE METAL HARDWARE THAT IS COLOR-MATCHED TO THE LAMP ASSEMBLY.

S SATELLIGHT, SPEAKER/LED LIGHT

- SHALL OPERATE ON A CAT 5e ALARM SUBNETWORK, WHICH IS DRIVEN FROM A DEVICE CONTROLLER.
- AUDIO OUTPUT FROM THE DEVICES SHALL BE SET BY THE SOFTWARE FROM THE CONTROLLER.
- AUDIO OUTPUT SHALL BE ADJUSTABLE ACROSS A 90 DECIBLE RANGE.
- THE LIGHTING OUTPUT SHALL INCREASE AUTOMATICALLY DURING THE FIRST FEW SECONDS OF THE ALARM SEQUENCE.
- SHALL BE MOUNTED IN CEILING TO PROVIDE ALARM COVERAGE THROUGHOUT THE STATION.
- ACOUSTICAL CEILING MOUNTING SECURES THE DEVICE TO THE T-BAR RAILS AND THE SUPERSTRUCTURE OF THE BUILDING.
- DRYWALL AND PLASTER CEILING MOUNTING HARDWARE INSTALLS DEVICES INTO THESE CEILINGS.



ALLRED & ASSOCIATES

ARCHITECTURE | PLANNING | INTERIOR DESIGN

580 BURLING STREET, SUITE 125, BROOMFIELD, COLORADO 80020 | PHONE: 303.465.4386 | WWW.ALLREDANDASSOCIATES.COM

PRE-FINAL (PERMIT SET) • JOB NO. 2309

CITY OF THORNTON
FIRE STATION #8
15343 MONACO STREET
THORNTON, COLORADO 80602

REVISION NAME	DATE

ISSUE DATE: 2024 0621

ALERTING DETAIL

FSA.04